

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of the Work: Earth work and other Works for Temporary tank for lord Ganesh Idols at behind Raghavendra Matta BEL 3rd Block in Ward No. 09 (Vidyaranyapura), Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	28.28	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed etc complete as per specifications and directions of engineer in charge of the work.	Cum	263.94	Rupees Two Hundred Sixty Three and Ninety Four Paise Only
2	214.50	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work.	Cum	137.80	Rupees One Hundred Thirty Seven and Eighty Paise Only
	214.50	Above 1.5 Mtrs Depth Add 25% Extra		172.25	Rupees One Hundred Seventy Two and Twenty Five Paise Only
3	945.00	Code 0516 - Providing Plastic Sheet etc complete as per specifications and directions of engineer in charge of the work.	Sqm	5.36	Rupees Five and Thirty Six Paise Only
4	165.00	Supply of water Through water Tank for filling Tank etc complete as per specifications and directions of engineer in charge of the work.	Each	360.00	Rupees Three Hundred Sixty Only
5	2.50	Providing Stone dust / Grit 4.75 mm to 0.075 mm to approach road and near immersion tank for levelling and to protect not to slipping SI No. 45 Code 400 metal Component etc complete as per specifications and directions of engineer in charge of the work.	Cum	1000.00	Rupees One Thousand Only
6	66.00	Hire charge of pumping water 3.5 KL/hr capacity Pump etc complete as per specifications and directions of engineer in charge of the work.	Hrs	42.00	Rupees Forty Two Only
7	165	Providing Causal Labours (Unskilled mazdoor Heavy) etc complete as per specifications and directions of engineer in charge of the work.	Nos	436.20	Rupees Four Hundred Thirty Six and Twenty Paise Only
8	800.00	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed vertically at intervals of 2.0 to 2.5 mtrs. C/C an horizontally at 0.50 mtr, above ground level, including fixing poles in the ground level for minimum depth of 3.0 mtr and tied with coir rope firmly including cost and conveyance of all materials, labour, lead and lift charges and complete on hire basis as per the engineer in charge.	Mtrs	65.00	Rupees Sixty Five Only

9	3300.00	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 30ft = 1200 sqft) etc complete as per specifications and directions of engineer in charge of the work.	Sft	8.00	Rupees Eight Only
10	1650.00	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) etc complete as per specifications and directions of engineer in charge of the work.	Rft	17.00	Rupees Seventeen Only
11	110	Hire Charge for Armless Plastic Chairs etc complete as per specifications and directions of engineer in charge of the work.	Nos	4.00	Rupees Four Only
12	55	Hire Charge for Wooden Table of Size 6ft x 2ft etc complete as per specifications and directions of engineer in charge of the work.	Nos	40.00	Rupees Forty Only
13	660.00	Hire Charge for supplying and running circuit service main with necessary messenger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathed aluminium wire etc complete as per specifications and directions of engineer in charge of the work.	Mtrs	9.00	Rupees Nine Only
14	55	1321 Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges etc complete as per specifications and directions of engineer in charge of the work.	Hrs	534.00	Rupees Five Hundred Thirty Four Only
15	66	Hire charges for Flood lighting arrangements for the stage and existing immersion Tank during night time etc complete as per specifications and directions of engineer in charge of the work.	Nos	285.00	Rupees Two Hundred Eighty Five Only
16	6	Hire charges compoment name 1087 Crane charges etc complete as per specifications and directions of engineer in charge of the work.	Day	3390.00	Rupees Three Thousand Three Hundred Ninety Only
17	220.00	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour etc complete as per specifications and directions of engineer in charge of the work.	Cum	213.06	Rupees Two Hundred Thirteen and Six Paise Only

[Signature]
Executive Engineer

Byatarayanapura Division
BBMP, Bangalore - 92

Note:

- 1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- 2 Unit rates and prices shall be quoted by the Tender in Indian rupees.
- 3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- 4 Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"No g correction NIL"
"DTS APPROVED"

[Signature]
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ಮಠ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.